

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	UTILITIES - BID ITEMS	BRIDGE NO. 1 (SHEET PILE WALL)	BRIDGE NO. 2 (GROUND ANCHORED)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
				4				4		EACH	CORPORATION STOP (1 1/2")	629.39	-					
				2				2		EACH	CORPORATION STOP (2")	629.39	-					
				1				1		LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42	-					
				2000				2000		TON	CRUSHED STONE BEDDING	629.54	48					
3300								3300		HR	UNIFORMED TRAFFIC OFFICERS	630.10	66					
3750								3750		HR	FLAGGERS	630.15	28					
							1	1		LS	FIELD OFFICE-ENGINEERS	631.10	-					
							1	1		LS	TESTING EQUIPMENT - CONCRETE	631.16	-					
							1	1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-					
							1	1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-					
	1040							1040		HR	EMPLOYEE TRAINEESHIP	634.10	EST.					
1								1		LS	MOBILIZATION / DEMOBILIZATION	635.11	-					
1								1		LS	TRAFFIC CONTROL	641.10	-					
1								1		LS	PUBLIC RELATIONS OFFICER	641.12	-					
4								4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	EST.					
10750								10750		LF	DURABLE 4" WHITE LINE	646.40	352					
10000								10000		LF	DURABLE 4" YELLOW LINE	646.41	210					
110								110		LF	DURABLE 8" WHITE LINE	646.42	10					
110								110		LF	DURABLE 8" YELLOW LINE	646.43	5					
325								325		LF	DURABLE 24" STOP BAR	646.46	7					
124								124		EACH	DURABLE LETTER OR SYMBOL	646.50	-					
600								600		LF	DURABLE CROSSWALK MARKING W/DIAGONAL LINES (MOD. - BLOCK TYPE)	646.51	27					
10750								10750		LF	TEMPORARY 4" WHITE LINE	646.60	352					
10000								10000		LF	TEMPORARY 4" YELLOW LINE	646.61	210					
110								110		LF	TEMPORARY 8" WHITE LINE	646.62	10					
110								110		LF	TEMPORARY 8" YELLOW LINE	646.63	5					
325								325		LF	TEMPORARY 24" STOP BAR	646.66	7					
124								124		EACH	TEMPORARY LETTERS OR SYMBOLS	646.70	-					
600								600		LF	TEMPORARY CROSSWALK MARKING W/DIAGONAL LINES (MOD. - BLOCK TYPE)	646.71	27					
				170				170		SY	GEOTEXTILE FABRIC FOR FILTERS	649.10	57					
				3200				3200		SY	GEOTEXTILE UNDER STONE FILL	649.31	108					
10490					600	1410		12500		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41	70					
				1100				1100		SY	GEOTEXTILE FOR SILT FENCE	649.51	141					
				50				50		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61	27					
		400						400		LB	SEED	651.15	87					
			400					400		LB	SEED-WINTER RYE	651.17	87					
			1375					1375		LB	FERTILIZER	651.18	70					
		550						550		LB	FERTILIZER (MOD. - MYCORRHIZAL)	651.18	50					
			6					6		TON	AGRICULTURAL LIMESTONE	651.20	.8					
			7					7		TON	HAY MULCH	651.25	1.8					

PROJECT NAME: **HARTFORD**
PROJECT NUMBER: **RS0113 (40)**
FILE NAME: z86c027quant.xls
PROJECT MANAGER: **KEN UPMAL, PE**
DESIGNED BY: **E. ATKINS**
QUANTITY SHEET #5
PLOT DATE: **02/28/2007**
DRAWN BY: **E. ATKINS**
CHECKED BY: **KO ISHIKURA**
SHEET **9** OF **239**