STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																			SIGN DETAIL	
												FLANGED CHANNEL			SQUARE STEEL (In)					TUBULAR ALUMINUM Ø (In)			TUBULAR STEEL Ø (In)					W-SHAPE STEEL						REMARKS		
		EA	WIDTH (In)	HEIGHT (In)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	lb/ft			1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0 MOD	FOUND-ATION	3.0	3.5	4.0	5.0	FTG. SIZE		WEIGHT	POST SIZE	SIGN	REQUIRED		DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												1.12	2.0	3.0	lb/ft					lb/ft				lb/ft				24"	30"						
												OPTION ITEMS			1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6									
40+50 LT	END	1	24	12	2.00						1			X		X		1															M4 - 6 TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
	CENTER LANE ONLY	1	24	36	6.00																												R3 - 9B (MOUNT W/ PREVIOUS SIGN) TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
41+05 RT	BEGIN	1	24	12	2.00						1			X		X		1															M4 - 11 TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
	CENTER LANE ONLY	1	24	36	6.00																												R3 - 9B (MOUNT W/ PREVIOUS SIGN) TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
42+70 LT	SPEED LIMIT 30	1	24	30	5.00						1			X		X		1															R2-1 TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 142
43+40 LT		1	36	36	6.75						2			X		X		2															S1-1 TYPE IX FLUORESCENT YELLOW-GREEN BACKGROUND RETRO-REFLECTIVE SHEETING		E - 153
	AHEAD	1	24	12	2.00																												W16-9p (MOUNT WITH PREVIOUS SIGN) TYPE IX FLUORESCENT YELLOW-GREEN BACKGROUND RETRO-REFLECTIVE SHEETING		MUTCD
43+50 RT	← HARTFORD AREA CTC						1				2			X		X		2															SALVAGED TO NEW POSTS		
44+10 LT	CENTER LANE ONLY	1	24	36	6.00						1			X		X		1															R3 - 9B TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
44+10 RT	CENTER LANE ONLY	1	24	36	6.00						1			X		X		1															R3 - 9B TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
25+37 LT SAUNDERS AVE	SAUNDERS AVE						1				1			X		X		1															SALVAGED TO NEW POSTS		E - 123
	STOP	1	30	30	6.25 ~~4.86~~																												R1 - 1 (MOUNT WITH PREVIOUS SIGN) TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 143
46+30 LT	CENTER LANE ONLY	1	24	36	6.00						1			X		X		1															R3 - 9B TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
47+10 RT	CENTER LANE ONLY	1	24	36	6.00						1			X		X		1															R3 - 9B TYPE III HIGH INTENSITY REFLECTIVE SHEETING		E - 140
47+29 LT	HARTFORD AREA CTC →						1				2			X		X		2															SALVAGED TO NEW POSTS TYPE III HIGH INTENSITY REFLECTIVE SHEETING		
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
														158.50			179.50																		
TOTALS		SF 58.61	SF		EA. 3	SF						FT 158.50			FT 179.50					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: HARTFORD
PROJECT NUMBER: RS 0113(40)

FILE NAME: z86c027tssum.DGN
PROJECT LEADER: KEN UPMAL
DESIGNED BY: E. ATKINS
PLOT DATE: 1/15/2007
DRAWN BY: E. ATKINS
CHECKED BY: K. ISHIKURA
SHEET 170 OF 239