



**GENERAL LANDSCAPE NOTES:**

- SEE ROADWAY TYPICAL SECTION SHEETS FOR SEEDING FORMULAS, FERTILIZER APPLICATION RATES, MULCH REQUIREMENTS ETC...
- SEE SPECIAL PROVISIONS FOR 65L18 FERTILIZER (MOD. - MYCORRHIZAL), THE APPLICATION OF MYCORRHIZAL FUNGI PER MANUFACTURER'S RECOMMENDATIONS AND 65L35 TOPSOIL (MOD), THE APPLICATION OF COMPOST.
- ORGANIC MATERIAL TOPSOIL, COMPOST AND NATIVE EXISTING SOIL SHALL BE TESTED AT AN APPROVED LAB PRIOR TO DELIVERY ON SITE AND INSTALLATION. ORGANIC MATTER SHALL BE A MINIMUM OF 5%.
- TOPSOIL (MOD.) BACKFILL WITH PLANTING MIX OF 1/2 SCREENED TOPSOIL, 1/4 COMPOST AND 1/4 NATIVE MATERIAL AS APPROVED BY THE ENGINEER. UNSUITABLE NATIVE MATERIAL SHALL BE REPLACED WITH IMPORTED APPROVED TOPSOIL AS DIRECTED BY ENGINEER.
- WATERING SHRUBS TO RECEIVE A MINIMUM OF 5 GALLONS AT EACH WATERING, TWICE WEEKLY DURING ESTABLISHMENT PERIOD. TREES TO RECEIVE A MINIMUM OF 10 GALLONS AT EACH WATERING, TWICE WEEKLY DURING ESTABLISHMENT PERIOD. CONTRACTOR SHALL MAINTAIN AND PROVIDE A LOG TO THE ENGINEER SHOWING AMOUNTS AND DATES OF WATERING FOR ALL PLANTINGS AND NOTING NATURAL RAINFALL EVENTS. WATERING SCHEDULE MAY BE ADJUSTED AS APPROVED BY THE ENGINEER. SEE SPECIAL PROVISIONS FOR ITEM 609.10 DUST CONTROL WITH WATER (MOD. - PLANT WATERING).
- TREE PIT WIDTH FOR TREES WITHIN PROJECT CONSTRUCTION LIMIT, THE DIMENSIONS OF BACKFILL PLANTING MIX ARE NOTED ON EACH PLAN SHEET. FOR ALL TREES TO BE PLANTED OUTSIDE PROJECT CONSTRUCTION LIMIT, THE PLANTING PIT SHALL BE THREE TIMES THE WIDTH OF THE ROOTBALL.
- TEMPORARY STORAGE OF ALL PLANTS SHALL BE LIMITED TO 45 DAYS FROM THE TIME OF DELIVERY UNTIL PLANTING.
- TREES DESIGNATED TO BE PROTECTED SHALL BE WATERED AT THE SAME RATE AND SCHEDULE AS NEW PLANTINGS.
- POOR NATIVE MATERIAL IN THE EVENT THAT THE NATIVE MATERIAL IS DEEMED UNACCEPTABLE BY THE ENGINEER, THE CONTRACTOR SHALL REPLACE THE UNSUITABLE NATIVE MATERIAL WITH A HOMOGENEOUS MIXTURE COMPRISING OF 75% TOPSOIL AND 25% COMPOST.

PROJECT NAME: HARTFORD  
PROJECT NUMBER: RS 0113(40)

FILE NAME: z86c027landdet.dgn  
PROJECT LEADER: KEN UPMAL  
DESIGNED BY: JANE BROWN

PLOT DATE: 2/28/2007  
DRAWN BY: E. ATKINS  
CHECKED BY: K. ISHIKURA  
SHEET 179 OF 239