

# DETOUR SIGN SUMMARY SHEET

SIGN ASSEMBLY DESIGNATION (SEE SHEET 20)	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS																REMARKS	SIGN DETAIL				
		E	A	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN			SALV TIS	NO. OF POSTS	SQUARE STEEL (in)				TUBULAR ALUMINUM (in)			TUBULAR STEEL (in)				W-SHAPE STEEL				SHSM	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER		
													1.75	2.0	2.5	ANCHOR	SLEEVE	3.0	4.0	4.0 MOD	FOUND-ACTION	3.0	3.5	4.0	5.0	FTG. SIZE					WEIGHT	POST SIZE
													lb/ft					lb/ft				lb/ft										
1.88	2.42	3.35	1.3	1.7	1.7	7.6	9.0	10.8	14.6																							
(K)		7	30	24	35.00					3		X		X												LOCATION AS SHOWN ON DETOUR MAP BLACK ON FLUORESCENT ORANGE	M4-9a(L)					
(L)		5	30	24	25.00					3		X		X												LOCATION AS SHOWN ON DETOUR MAP BLACK ON FLUORESCENT ORANGE	M4-9a(R)					
(M)		10	30	24	50.00					10		X		X												LOCATION AS SHOWN ON DETOUR MAP BLACK ON FLUORESCENT ORANGE	M4-9a					
(N)		2	24	12	4.00					2		X		X												LOCATION AS SHOWN ON DETOUR MAP BLACK ON FLUORESCENT ORANGE	M4-8b					
(O)		1	60	30	12.50																					3.3 MILES LOCATION AS SHOWN ON DETOUR MAP SIGN MOUNTED ON TYPE III BARRICADE	R11-3a					
(O)		1	60	30	12.50																					0.5 MILES LOCATION AS SHOWN ON DETOUR MAP SIGN MOUNTED ON TYPE III BARRICADE	R11-3a					
(O)		2	60	30	25.00																					100 FEET LOCATIONS AS SHOWN ON DETOUR MAP SIGNS MOUNTED ON TYPE III BARRICADE	R11-3a					

NOTES

- FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VAOT "SIGN POST DESIGN GUIDELINE."
- ALL SIGNS SHOWN ARE FOR INFORMATIONAL PURPOSES. ALL SIGNS, POSTS, AND ANCHORS WILL BE PAID UNDER ITEM 900.645, "SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)". SEE TRAFFIC CONTROL NOTES FOR ADDITIONAL INFORMATION.

PROJECT NAME: ST. JOHNSBURY  
PROJECT NUMBER: BF 7000(20)  
FILE NAME: 86e048/cos/z86e048bdr+top.dgn PLOT DATE: 10/26/2016  
PROJECT LEADER: J.BYATT DRAWN BY: P. McKECHNIE  
DESIGNED BY: M.HALEY CHECKED BY: P.SHEDD  
DETOUR SIGN SUMMARY SHEET 2 SHEET 22 OF 70