STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

SIGNS & POST INSTALLED 10-20-06

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL 4.7 kg/m	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.9	63 kg/m 5.0	ANCHOR	SLEEVE	NEW SIGN POSTS TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
ℳ STA 0+211.274	STOP	1	750	750	0.563						1		4.26																				RI-1		E-143M
	1000 1206 0120	1	150	250	0.038																															E-138M
℄ STA 5+005.796	WARD HILL						1			1																										
℄ STA 5+011.585	DUXBURY WOODS						1			+			3.66M																				OWNER REMOVED AFTER ERECTION		
℄ STA 5+020.358	LEGAL LOADS LIMIT 34,000 POUNDS	1	600	750	0.450						1		4.26																				VR-017		E-141M
	PUBLIC NOTICE						1			+																							ON LLL SIGN NEW POST		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TOTALS	m^2	m^2	EA.	m^2		m	m	EA	kg	kg	EA.	kg	EA.	EA.	kg
	1.884														

SIGN SUMMARY SHEET

PROJECT NAME: DUXBURY
PROJECT NUMBER: STP 013-4(24)

FILE NAME: /str5/86e059/se059sgn.dgn
PROJECT LEADER: C. KELLER
DESIGNED BY: B. NYQUIST
se059sg2.1

PLOT DATE: 20-OCT-2005
DRAWN BY: J. GILMORE
CHECKED BY: T. SUMNER
SHEET 44 OF 62