DETAILED SUMMARY OF QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COMMON EXCAVATION, ITEM #203.15
2201	CY	MAINLINE
81	CY	TH #6
10	CY	DRIVES
8	CY	ROUNDING
2300	CY	TOTAL
		SAND BORROW, ITEM #203.31
1233	CY	MAINLINE
7	CY	ROUNDING
1240	CY	TOTAL
		FINE GRADING-SUBGRADE, ITEM #203.40
2780	SY	MAINLINE
668	SY	TH #6
26	SY	DRIVES
16	SY	ROUNDING
3490	SY	TOTAL
		TRENCH EXCAVATION OF EARTH, ITEM #204.20
132	CY	DESIGNED DRAINAGE
71	CY	UNDERDRAIN
25	CY	TEMPORARY EROSION CONTROL
11	CY	ROUNDING
239	CY	TOTAL
		COLD PLANING-BITUMINOUS PAVEMENT, ITEM #210.10
322	SY	MAINLINE
56	SY	TH #6
12	SY	ROUNDING
390	SY	TOTAL
		SUBBASE OF DENSE GRADED CRUSHED STONE ITEM #301.35
2313	CY	MAINLINE
267	CY	TH #6
90	CY	TEMPORARY EROSION CONTROL
20	CY	ROUNDING
2690	CY	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS			
		EMULSIFIED ASPHALT, ITEM #404.65			
4.5	CWT	MAINLINE			
0.8	CWT	TH #6			
0.7	CWT	ROUNDING			
6	CWT	TOTAL			
		BITUMINOUS CONCRETE PAVEMENT ITEM #406.25			
			TYPE III	II	I
711	TON	MAINLINE	176	218	317
200	TON	DETOUR (SEE NOTE)		200	
122	TON	TH #6	55	67	
2	TON	DRIVES	2		
15	TON	ROUNDING			
1050	TON	TOTAL			
		NOTE: SEE NOTE 30 ON SHEET 50 OF 79			

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: CHESTER	PROJECT NO.: BRF 025-1(35)
DESIGN FILE NAME: M:\ 154900 VAOT-Chester Curv\HWY\DRAW\zf134frm.dgn	
IPARM FILE NAME: zf134qs5.1	PLOT DATE: 04-JUN-2003
SURVEYED BY: SHERIDAN	SURVEY DATE: 8/90
SQUAD LEADER: PORTALUPI	DRAWN BY: L. BULLOCK
	SHEET: 10 OF 79