

Gore Area

Gore areas to include 8 inch channelizing line and 4" dashed line
See Standard Sheet E-191.

D. Edge Lines

~~When specified, edge lines are not required until completion of the project. Edge lines should be applied where traffic volumes are high and/or a delay of several days is anticipated. In these instances, paint or RPM's can be used as the interim marking material to be paid under the appropriate bid item. RPM's should be retro-reflective temporary markers on a 5' spacing pattern and the same color as the line they are substituting for.~~

- E. Prior to acceptance, the pavement markings shall be completed for the entire project by the Contractor as detailed on the plans or directed by the Resident Engineer.