QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

F 026-1(31)S	F 026-2(3)S	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
35	335	370	CY	DENSE GRADED CRUSHED STONE	301.35	7
50	35	85	TON	AGGREGATE SHOULDERS	402.12	3
10	10	20	CWT	EMULSIFIED ASPHALT	404.65	4
500	625	1125	TON	BITUMINOUS CONCRETE PAVEMENT	406.25	33
15	30	45	HR	POWER GRADER RENTAL	608.15	EST.
25	55	80	HR	ALL PURP. EXCAVATOR RENTAL, TYPE I	608.25	EST.
10	10	20	HR	POWER BROOM RENTAL	608.30	EST.
25	55	80	HR	TRUCK RENTAL	608.37	EST.
115	0	115	LF	REMOVING AND RESETTING CURB	616.40	-
50	50	100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
100	100	200	HR	FLAGGERS	630.15	EST.
0.5	0.5	1	LS	FIELD TESTING	631.15	EST.
0.5	0.5	1	LS	MOBILIZATION	635.10	EST.
330	705	1035	LF	PAINTED CURB	646.21	5
510	470	980	LF	DURABLE 4'' WHITE LINE	646.30	4
1520	1430	2950	LF	DURABLE 4'' YELLOW LINE	646.31	11
125	200	325	LF	DURABLE 8'' WHITE LINE	646.34	5
190	210	400	LF	DURABLE 8'' YELLOW LINE	646.35	18
50	0	50	LF	DURABLE 24'' STOP BAR	646.40	4
2	4	6	EA	DURABLE ARROW MARKING	646.42	-
12	21	33	EA	DURABLE LETTER IN WORD MARKING	646.44	-
2370	3130	5500	LF	TEMPORARY 4'' WHITE LINE	646.50	20
2420	3280	5700	LF	TEMPORARY 4'' YELLOW LINE	646.51	10
100	150	250	LF	TEMPORARY 8'' WHITE LINE	646.54	10
50	0	50	LF	TEMPORARY 24'' STOP BAR	646.60	4
2	4	6	EA	TEMPORARY ARROW MARKING	646.62	-
0	40	40	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.80	-
5	5	10	CY	TOPSOIL	651.35	-
65	185	250	SF	TRAFFIC SIGNS, TYPE A	675.20	1.4
380	160	540	SF	TRAFFIC SIGNS, TYPE B	675.21	12
220	750	970	LB	FLANGED CHANNEL SIGN POST	675.30	11.5
0	750	750	LB	W-SHAPED STEEL SIGN POST	675.31	3
0	60	60	LB	TUBULAR ALUMINUM SIGN POSTS	675.32	3
0	2	2	EA	FOUNDATION FOR W-SHAPE STEEL POST 24'' DIAMETER	675.41	-
24	38	62	EA	REMOVING SIGNS	675.50	-
0	1	1	EA	ERECTING SALVAGED SIGNS	675.60	-
0	40	40	EA	REM. & REPLACE REFLECTOR UNITS (MOD)	676.15	3

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		F 026-1(31)S BITUMINOUS CONCRETE PAVEMENT
22	TON	SHOULDER AND ISLAND REPAIR 5'' (2-LIFTS) TYPE I
89	TON	LEVELING TYPE III
364	TON	PAVEMENT 1-1/4'' TYPE III
25	TON	ROUNDING
500	TON	TOTAL
		F 026-2(3)S BITUMINOUS CONCRETE PAVEMENT
79	TON	SHOULDER AND ISLAND REPAIR 5'' (2-LIFTS) TYPE I
18	TON	SHOULDERS 2'' TYPE II
106	TON	LEVELING TYPE III
412	TON	PAVEMENT 1-1/4'' TYPE III
10	TON	ROUNDING
625	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME NEWBURY
PROJECT NUMBER F 026-1(31)S F 026-2(3)S

1-19-88 PAVE87QS
SHEET 4 OF 43 SHEETS