TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	℄	QUANTITY LT	QUANTITY ℄	QUANTITY RT		TOTALS
1.055	1.140	SOLID	DASHED		449		110		559
1.140	1.383	SOLID	SOLID		1283		1283		2566
									3125
		ASSUME 100% LOSS DUE TO LEVELING							X 2
									6250
		LESS BREAK AT JCT VT 107							-80
									6170
								ROUNDING	30
									6200 LF
		ITEM 646.40 DURABLE 24" STOP BAR							18 LF
		ITEM 646.44 DURABLE LETTER IN WORD MARKING (STOP @ JCT VT 107) (STOP AHEAD @ MM 1.23)							13 EA

TEMPORARY 4" WHITE LINE

1.055	1.383	SOLID	SOLID		1732		1732		3464
								ROUNDING	36
									3500 LF

PROJECT BETHEL

NO. HMA 2918

SHEET 33 OF 34 SHEETS