

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	℄	QUANTITY LT	QUANTITY ℄	QUANTITY RT	TOTALS
0.220	0.46	Solid	Solid		1267		1267	2534
0.46	0.56	Solid	Broken		528		132	660
0.56	1.32	Solid	Solid		4013		4013	8026
1.32	1.48	Broken	Solid		238		950	1188
1.48	1.73	Solid	Solid		1214		1214	2428
1.73	1.87	Solid	Broken		739		185	924
1.87	1.88			Broken	.	40		40
1.88	2.01	Broken	Solid		145		581	726
2.01	2.05			Broken		53		53
2.05	2.14	Solid	Broken		475		119	594
2.14	2.16	Solid	Solid		106		106	212
2.16	2.28	Broken	Solid		158		634	792
2.28	2.55	Solid	Solid		1426		1426	2852
2.55	2.624	Solid	Broken		391		98	489
								21518
		Assume 100% Loss for Leveling					x	2
								43036
		Deduct for intersections with	sideroads ⇒					- 1280
		(8x40x2)x2						41756
							Red	44
							USE ⇒	41800 LF

TEMPORARY 4" WHITE LINE

0.220	2.624	Solid	Solid		12693		12693	25386
		Deduct for intersection with 2 gravel roads ⇒						- 80
								25306 LF
							USE	25300 LF