

TEMPORARY 4" YELLOW LINE									
MILE	MILE	LT	RT	ℓ	QUANTITY LT	QUANTITY ℓ	QUANTITY RT		TOTALS
0.000	1.982	Solid	Solid		10465		10465		20930
0.000	0.69	Solid	Solid		3643		3643		7286
0.69	0.97	Solid	Broken		1320		330		1650
0.97	1.11	Broken	Solid		211		845		1056
1.11	1.21	Solid	Solid		581		581		1162
1.21	1.33	Broken	Solid		158		634		792
1.33	2.12	Solid	Solid		4330		4330		8660
2.12	2.24	Solid	Broken		475		119		594
2.24	2.330	Solid	Solid		475		475		950
									43080
		Assume 100% Loss for Leveling =>					X		2
									86160
		- INTERSECTION WITH 6 SIDE ROADS							
		(7x40x2)x2						-	1120
									85040
							Rndy		60
							Use =>		85100 LF
TEMPORARY 4" WHITE LINE									
0000	1.982	Solid	Solid		10465		10465		20930
0.000	2.330	Solid	Solid		12302		12302		24604
		Deduct for intersection with 5 Gravel side roads						-	200
									45334 LF
							Rndy		66
							Use =>		45400
PROJECT ST. GEORGE - WILLISTON					NO. HMA 2915				
					SHEET 23 OF 31 SHEETS				