

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	Q	QUANTITY LT	QUANTITY Q	QUANTITY RT	TOTALS	
1.322	2.750	SOLID	SOLID		7540		7540	15080	
2.750	2.900	SOLID	BROKEN		792		198	990	
2.900	3.020			BROKEN		158		158	
3.020	3.190	BROKEN	SOLID		225		898	1123	
3.190	3.480	SOLID	SOLID		1531		1531	3062	
3.480	3.610	SOLID	BROKEN		686		172	858	
3.610	3.660			BROKEN		53		53	
3.660	3.780	BROKEN	SOLID		172		686	858	
3.780	7.965	SOLID	SOLID		22097		22097	44194	
							TOTAL	66376	
		ASSUME	100%	LOSS	DUE TO	LEVELING	X 2		
								132752	
		DEDUCT FOR INTESECTIONS WITH 23 SIDEROADS							-3680
							ROUNDING	28	
							USE =>	129100 LF	
		ITEM 646.40 DURABLE 24" STOP BAR (MM 1.33)							12 LF
		ITEM 646.44 DURABLE LETTER IN WORD MARKING							13 EA
		(STOP @ MM 1.33 -JCT VT 106)							
		(STOP AHEAD @ MM 1.46)							

TEMPORARY 4" WHITE LINE

1.322	7.965	SOLID	SOLID		35075		35075	70150	
		DEDUCT FOR INTERSECTIONS WITH 24 SIDEROADS							- 960
								69190	
							ROUNDING	60	
								69250	

PROJECT WEATHERSFIELD

NO. HMA 2931

SHEET 31 OF 33 SHEETS