

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C. E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	EPSC PLAN	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								30			30		SY	TEMPORARY EROSION MATTING	653.20				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								5			5		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								282			282		LF	BARRIER FENCE	653.50				
								92			92		LF	PROJECT DEMARCATION FENCE	653.55				
							1				1		SF	TRAFFIC SIGNS, TYPE A	675.20				
							46				46		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							4				4		EACH	REMOVING SIGNS	675.50				
							4				4		EACH	ERECTING SALVAGED SIGNS	675.60				
							450				450		LF	ELECTRICAL CONDUIT (2"X)PVC)	678.21				
							1				1		EACH	TEMPORARY TRAFFIC SIGNAL SYSTEM	678.40				
									13		13		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
									102		102		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, EARTH)	900.640				
									38		38		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, ROCK)	900.640				
									1		1		LS	SPECIAL PROVISION (COVERED WALKWAY)	900.645				
										1	1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
							1				1		LS	SPECIAL PROVISION (TEMPORARY WATER MAIN)(10" HDPE)	900.645				
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
							1				1		LS	SPECIAL PROVISION (WATER MAIN ON BRIDGE)(12" D.I.)	900.645				
							1				1		LU	SPECIAL PROVISION (INCENITVE/DISINCENTIVE)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
							290				290		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: STOWE
 PROJECT NUMBER: BRF 0235 (II)
 FILE NAME: s87e052forms.dgn PLOT DATE: 28-JUL-2014
 PROJECT LEADER: C. CARLSON DRAWN BY: M. LONGSTREET
 DESIGNED BY: D. PETERSON CHECKED BY: J. LACROIX
 QUANTITY SHEET 3 SHEET 8 OF 64