STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
REV 69+01 RT	NO PARKING THIS SIDE OF STREET						1				~~1~~			~~X~~																		MOUNTED ON SIGNAL POLE		
	BUS STOP C.C.T.A.						1																									MOUNTED ON SIGNAL POLE		
REV 70+50 LT	BID	1	24"	6"	1.00																											D1-1B (L)	142	
	BIKE ROUTE / BIKE ROUTE	2	24"	18"	6.00						1			X																		D11-1 BACK TO BACK		E-131B
	DOWNTOWN 2 ↑ / ← WINOOSKI	2	24"	6"	2.00																											D1-1B BACK TO BACK M4-12	142	E-131B
		SUBTOTAL			9.00		2							29																					
	SUBTOTAL SHEET 141A				60.26									114																					
	SUBTOTAL SHEET 141B				48.38		2							149																					
	SUBTOTAL SHEET 142C				59.13		4	8.00						149																					
	SUBTOTAL SHEET 141D				53.25		1							174																					
	SUBTOTAL SHEET 141E				31.00		4	8.00						123																					
	SUBTOTAL SHEET 141F				54.25		2							141																					
	SUBTOTAL SHEET 141G				44.75		4							146																					
	SUBTOTAL SHEET 141H				56.00		3							201																					
	SUBTOTAL SHEET 141I				9.00		2							29																					
												FT	FT	FT 1226	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
		PROJECT TOTALS			SF 416.02	SF	EA. 22	SF 16.00				FT 1226			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BURLINGTON	PROJECT NO. : MEGC 5000(15)
DESIGN FILE NAME:	
IPARM FILE NAME:	PLOT DATE:
SURVEYED BY: CLD	SURVEY DATE:
SQUAD LEADER: JAW	DRAWN BY: TPL
	SHEET: 141I OF 252