

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY ¢	QUANTITY RT	TOTALS
3.600	3.64	Solid	Solid	211		211	422
3.64	3.70	Solid	Dash	317		79	396
3.70	3.96	Dash	Dash		343		343
3.96	4.08	Dash	Solid	158		634	792
4.08	4.51	Solid	Solid	2270		2270	4540
4.51	4.63	Solid	Dash	634		158	792
4.63	4.77	Dash	Solid	185		739	924
4.77	5.06	Solid	Solid	1531		1531	3062
5.06	5.20	Solid	Dash	739		185	924
5.20	5.32	Dash	Dash		158		158
5.32	5.853	Solid	Solid	2814		2814	5628
						Subtotal	17981
				Assume 100% Loss Due to Leveling			17981
				Minus 8 Rdwy Openings @ 80' Ea			-1280
				x2 Courses of Pavement			
						TOTAL	34682

TEMPORARY 4" WHITE LINE

3.600	5.853	Solid	Solid	11896		11896	23792

PROJECT Brandon

NO. HMA 2853
 SHEET 5 OF 7 SHEETS
 SHEET 32 OF 75 SHEETS