

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT	QUANTITY LT	QUANTITY C	QUANTITY RT	TOTALS
Essex	0.00	0.87	S	S	4594		4594	9188
	0.87	1.02	S	S	792		792	1584
	1.02	1.49	S	S	2482		2482	4964
	1.49	1.55	S	D	317		79	396
	1.55	1.76	D	S	277		1109	1386
	1.76	1.88	D	S	158		634	792
	1.88	2.27	S	S	2059		2059	4118
	2.27	2.42	S	S	792		792	1584
	2.42	2.55	D	S	172		686	858
	2.55	2.70	S	D	792		198	990
	2.70	4.38	S	S	8870		8870	17740
	4.38	0.00	S	D	106		27	133
Westford	0.00	0.04	S	D	211		53	264
	0.04	0.22	D	D		238		238
	0.22	0.34	D	S	158		634	792
	0.34	0.62	S	S	1478		1478	2956
	0.62	0.76	S	D	739		185	924
	0.76	0.97	D	D		277		277
	0.97	1.10	D	S	171		686	857
	1.10	1.300	S	S	1056		1056	2112
							SUBTOTAL	= 52153
							ASSUME 100% LOSS DUE TO LEVELING	= 52153
							MINUS 6 TH'S @ 80' EACH	= -960
							SUBTOTAL	= 103346
							ROUNDING	= 4
							TOTAL	= 103350

TEMPORARY 4" WHITE LINE

Essex	0.00	4.400	S	S	23232		23232	46464
Westford	0.00	1.300	S	S	6864		6864	13728
							SUBTOTAL	60192
							ROUNDING	8
							TOTAL	60200
							12 L.F. OF DURABLE STOP BAR @ MM 0.00 IN ESSEX =	12 L.F. STOP BAR
							"SCHOOL" DURABLE LETTERS @ MM 0.08 & MM 0.28 IN ESSEX =	12 DURABLE LETTERS

PROJECT Essex - Westford

NO. HMA 2835 & 2832

SHEET 16 OF 60 SHEETS