

TEMPORARY 4" REFLECTORIZED YELLOW LINE D = DASHED LINE
S = SOLID LINE

	MILE	MILE	LT	RT	Q	QUANTITY LT	QUANTITY Q	QUANTITY RT		TOTALS
MORRISTOWN	2.37	2.45	D	S		106		422		528
	2.45	3.04	S	S		3115		3115		6230
	3.04	3.18	S	D		739		185		924
	3.18	3.25			D		92			92
	3.25	3.34	D	S		119		475		594
	3.34	4.11	S	S		4066		4066		8132
	4.11	4.26	S	D		792		198		990
	4.26	4.85	S	S		3115		3115		6230
								SUBTOTAL	=	23,720
					ASSUME 100% LOSS DUE TO LEVELING				= +	23,720
	MINUS	3 ROADWAY OPENINGS AT 80' EACH			X 2 COURSES OF PAVE:					- 480
								SUB-TOTAL	=	46,960 LF
								ROUND	=	40
								TOTAL		47,000

TEMPORARY 4" REFLECTORIZED WHITE LINE

	2.374	4.851	SOLID	SOLID		13,078		13,078		26,156