TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT		QUANTITY LT	QUANTITY ℄	QUANTITY RT		TOTAL
	WILMINGTON 7.118	MARLBORO 0.470	SOLID	SOLID		3315.84		3315.84		6631 L
									SUBTOTAL	6631 L
	*	DEDUCT 80' FOR		EACH	INTERSECTION		WITH			
		TOWN HIGHWAYS			(2 *	80')	= 160 LF			-160 LF
									SUBTOTAL	6472 L
										* 2
	*	ASSUME 100%			LOSS	OF ℄	DURING			
		LEVELING			2 *	6472	=			12,944 L

TEMPORARY 4" WHITE LINE

PROJECT WILMINGTON - MARLBORO

NO. HMA 2851 SHT 57 OF 6

SHEET 8 OF 8 SHEETS