

TEMPORARY 4" REFLECTORIZED YELLOW LINE D = DASHED LINE
S = SOLID LINE

	MILE	MILE	LT	RT	℄	QUANTITY LT	QUANTITY ℄	QUANTITY RT	TOTALS
MORRISTOWN	2.37	2.45	D	S		106		422	528
	2.45	3.04	S	S		3115		3115	6230
	3.04	3.18	S	D		739		185	924
	3.18	3.25			D		92		92
	3.25	3.34	D	S		119		475	594
	3.34	4.11	S	S		4066		4066	8132
	4.11	4.26	S	D		792		198	990
	4.26	4.85	S	S		3115		3115	6230
							SUBTOTAL	=	23,720
					ASSUME 100% LOSS DUE TO LEVELING			= +	23,720
	MINUS	3 ROADWAY OPENINGS AT 80' EACH			X 2 COURSES OF PAVE:				- 480
							SUB-TOTAL	=	46,960 LF
							ROUND	=	40
							TOTAL		47,000

TEMPORARY 4" REFLECTORIZED WHITE LINE

	2.374	4.851	SOLID	SOLID		13,078		13,078	26,156