

MILE	MILE	LT	RT	¢	QUANTITY LT	QUANTITY ¢	QUANTITY RT	TOTALS FEET
6.000	6.73	Solid	Solid		3854		3854	7708
6.73	6.89	Broken	Solid		211		845	1056
6.89	7.13	Solid	Solid		1267		1267	2534
7.13	7.22	Solid	Broken		475		119	594
7.22	7.27			Broken		66		66
7.27	7.41	Broken	Solid		185		739	924
7.41	7.43	Solid	Solid		106		106	212
7.43	7.60	Solid	Broken		898		225	1123
7.60	7.898	Solid	Solid		1573		1573	3146
								17363
		Assume 50% lost during leveling						
					$17363 \times 0.5 =$			8682
								26045
		4 town roads @ 40' each:				4x40'x2		- 320
								25725
					Use			<u>25750 LF</u>

6.000	7.898	Solid	Solid		10021		10021		20042
		Assume no losses, but deduct for intersection with 4 gravel roads,							
		total of 110'							
									- 110
									19932
						Use			19950LF

NO. HMA 2862
SHEET 10 OF 26 SHEETS