

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT	¢	QUANTITY LT	QUANTITY ¢	QUANTITY RT	TOTALS FEET
	8.148	8.89	Solid	Solid		3918		3918	7836
	8.89	9.01	Broken	Solid		159		634	793
	9.01	10.16	Solid	Solid		6072		6072	12144
	10.16	10.27	Solid	Broken		581		145	726
	10.27	10.40			Broken		172		172
	10.40	10.498	Broken	Solid		129		517	646
	0.00	0.13	Solid	Solid		686		686	1372
	0.13	0.23	Solid	Broken		528		132	
	0.23	0.31			Broken		106		106
	0.31	0.45	Broken	Solid		185		739	924
	0.45	0.75	Solid	Solid		1584		1584	3168
	0.00	1.613	Solid	Solid		8517		8517	17034
									44921
			assume 50% lost during leveling						
						44921 x 0.5 =			22461
									67382
			10 town roads @ 40' each: 10 x 40' x 2						- 800
									66582
							Use		66600.4

TEMPORARY 4" WHITE LINE

	8.148	10.498	Solid	Solid		12408		12408	24816
	0.00	0.75	Solid	Solid		3960		3960	7920
	0.00	1.613	Solid	Solid		8517		8517	17034
									49770
			assume no losses, but deduct for intersection						- 310
			with 6 gravel roads, total of 310'						49460