

PROJECT TROY ROUTE 105 PROJECT # HMA 2831

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT.	RT.	QTY. LEFT	Q (SINGLE DASH)	QTY. RT.	TOTAL (LF)
3.098	4.21	S	S	5871		5871	11,742
4.21	4.38	S	D	898		225	1122
4.38	4.58	D	S	264		1056	
4.58	4.76	S	S	950		950	1900
4.76	4.87	S	D	581		145	726
4.87	4.91	S	S	211		211	422
4.91	5.06	D	S	198		792	990
5.06	5.14	S	S	422		422	844
5.14	5.30	D	D		211		211
5.30	5.75	S	S	2376		2376	4752
							24029
@ 5.60 RT			ASSUME	50% LOST	DURING		12014
RXR MARKING			LEVELING				36043
@ 5.85 LT			7 TOWN ROADS @ 40' EACH				560
RXR MARKING			7X40X2				35,483
						ROUNDING +17	17
							35,500

TEMPORARY 4" WHITE LINE

MILE	MILE	LT.	RT.	QTY. LEFT	SINGLE DASH	QTY. RT.	TOTAL (LF)
3.098	5.750	SOLID	SOLID	14003		14003	28006
					SHEET	25 OF 26	SHEETS