

TEMPORARY 4" YELLOW LINE

S = SOLID LINE
B = DASHED LINE

	MILE	MILE	LT	RT		QUANTITY LT	QUANTITY C	QUANTITY RT		TOTALS
LYNDON	3.346	4.13	S	S		4140		4140		8280
	4.13	4.15	S	B		106		27		133
	4.15	4.28	B	S		172		686		858
	4.28	4.83	S	S		2904		2904		5808
WHEELDOCK	0.00	0.54	S	S		2851		2851		5702
	0.54	0.67	S	B		686		172		858
	0.67	0.91	S	S		1267		1267		2534
	0.91	1.04	B	S		172		686		858
	1.04	1.57	S	S		2798		2798		5596
SHEFFIELD	0.00	1.25	S	S		6600		6600		13200
								SUBTOTAL		43827
								ASSUME 50% LOSS @ LEVELING		+ 21914
								SUBTOTAL		65741
								rounding		9
								TOTAL		65750 LF

TEMPORARY 4" WHITE LINE

	MILE	MILE	LT.	RT.		QUANTITY LT.	QUANTITY C	QUANTITY RT.		
LYNDON	3.346	4.83	S	S		7836		7836		15672
HARDWICK	0.00	1.57	S	S		8290		8290		16580
STOWE	0.00	1.25	S	S		6600		6600		13200
								TOTAL		45452
								SAY		45450

PROJECT LYNDON - SHEFFIELD

NO. HMA 2834

SHEET 9 OF 30 SHEETS