

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	¢	QUANTITY LT	QUANTITY ¢	QUANTITY RT	TOTALS FEET	
3.130	3.54	Solid	Solid		2165		2165	4330	
3.54	3.70	Solid	Broken		845		211	1056	
3.70	4.00	Solid	Solid		1584		1584	3168	
4.00	4.13	Broken	Solid		172		686	858	
4.13	5.99	Solid	Solid		9821		9821	19642	
5.99	6.14	Solid	Broken		792		198	990	
6.14	6.30			Broken		211		211	
6.30	6.44	Broken	Solid		185		739	924	
6.44	6.76	Solid	Solid		1690		1690	3380	
6.76	6.87	Solid	Broken		581		145	726	
6.87	7.06			Broken		251		251	
7.06	7.20	Broken	Solid		185		739	924	
7.20	7.350	Solid	Solid		792		792	1584	
0.00	0.112	Solid	Solid		591		591	1182	
								<u>39226</u>	
		Assume 50% lost during leveling							
					39226	x 0.5	=	19613	
								<u>58839</u>	
		3 town roads & VT 58 twice							
		@ 40' each : 5 x 40' x 2							- 400
								<u>58439</u>	
						Use		<u>584501</u>	

TEMPORARY 4" WHITE LINE

3.130	7.350	Solid	Solid		22282		22282	44564
0.00	0.112	Solid	Solid		591		591	1182
								45746
		Assume no losses, but deduct for intersection with 4 town roads & traffic island, total of 230'						- 230
								45516
						Use		<u>455501</u>