

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT	¢	QUANTITY LT	QUANTITY ¢	QUANTITY RT		TOTALS FEET
	5.984	6.09	Solid	Solid		560		560		1120
	6.09	6.22	Solid	Broken		686		172		858
	6.22	6.33			Broken		145			145
	6.33	6.46	Broken	Solid		172		686		858
	6.46	6.67	Solid	Solid		1109		1109		2218
	6.68	7.75	Solid	Solid		5650		5650		11300
	7.75	7.88	Solid	Broken		686		172		858
	7.88	7.93			Broken		66			66
	7.93	8.01	Broken	Solid		106		422		528
	8.01	8.70	Solid	Solid		3643		3643		7286
	8.70	8.86	Solid	Solid		845		845		1690
	8.86	8.89	Solid	Solid		158		158		316
	8.89	9.03	Solid	Broken		739		185		924
	9.03	9.09			Broken		79			79
	9.09	9.21	Broken	Solid		158		634		792
	9.21	9.47	Solid	Solid		1373		1373		2746
	9.47	9.57	Solid	Solid		528		528		1056
	9.57	9.69	Broken	Solid		158		634		792
	9.69	9.899	Solid	Solid		1104		1104		2208
										35840
			Assume 50% lost during leveling							
						35840	x 0.5	=		17920
										53760
			6 town roads @ 40' each: 6x40'x2							- 480
										53280L

TEMPORARY 4" WHITE LINE

	5.984	9.899	Solid	Solid		20671		20671		41342
			Assume no losses but deduct							
			for intersection with 4 gravel							- 460
			roads, total of 460'							40882
						Use				40900L

PROJECT BARTON

NO. HMA 2838

SHEET 20 OF 26 SHEETS