

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	☒	QUANTITY LT	QUANTITY ☒	QUANTITY RT	TOTALS FEET	
4.515	4.75	Solid	Solid		1241		1241	2482	
4.75	4.90	Solid	Broken		792		198	990	
4.90	5.23	Solid	Solid		1742		1742	3484	
5.23	5.37	Solid	Broken		739		185	924	
5.37	5.41			Broken		53		53	
5.41	5.51	Broken	Solid		132		528	660	
5.51	5.765	Solid	Solid		1346		1346	2692	
								11285	
		assume 50% lost during leveling							
		11285 x 0.5 =							5643
								16928	
		2 town roads @ 40' each; 2x40'x2							- 160
								16768	
					Use			<u>16800 LF</u>	

TEMPORARY 4" WHITE LINE

4.515	5.765	Solid	Solid		6600		6600	13200	
		assume no losses, but deduct for intersection with 2 gravel roads total of 65'							- 65
								<u>13135 LF</u>	

PROJECT GLOVER

NO. HMA 2856  
SHEET 25 OF 26 SHEETS