


PROJECT DESCRIPTION AND LOCATION



TRAFFIC DATA

1986 AADT = 2020


V = 50 MPH

PROJECT INCLUDES OVERLAYING THE EXISTING BITUMINOUS CONCRETE PAVEMENT (SHOULDERS INCLUDED) WITH 1 1/4" BIT. CONC. PAVT. EXISTING GRAVEL SHOULDERS WILL BE EXCAVATED, FILLED WITH AGGREGATE SHOULDER MATERIAL, AND OVERLAYED WITH 1 1/4" BIT. CONC. PAVT.

END PROJECT HMA 2819
MM 6.800

TAPER 1 1/4" OVERLAY TO 0" OVER *
200' BEFORE & AFTER BR #2 OVER
VT. 142. DO NOT PAVE UNDER RR BRIDGE

BEGIN PROJECT HMA 2819
MM 0.000



*NOTE: MIN. 13.8' CLEARANCE IS TO BE MAINTAINED UNDER BR #2 OVER VT 142.

ON VT. RT. 142, BEGINNING AT THE MASSACHUSETTS-VERMONT BORDER, AND EXTENDING NORTHERLY 6.800 MILES.

LENGTH OF PROJECT : 6.800 MI
= 35,704.0 FT.