## TEMPORARY 4" YELLOW LINE

| | MILE | MILE | LT | RT | | QUANTITY LT | QUANTITY ℄ | QUANTITY RT | | TOTAL: |
|---|---|---|---|---|---|---|---|---|---|---|
| | 4.500 | 5.157 | SOLID | SOLID | | 3469 | | 3469 | | 6938 LF |
| | | | | | | | | | SUBTOTAL | 6938 LF |
| | * | DELETE | 40' | FOR INTERSECTION | | w/ T. H. # | 26 | | | |
| | | | 40 * 2 LINES = | | | 80 LF | | | | -80 LF |
| | | | | | | | | | SUBTOTAL | 6858 LF |
| | * | ASSUME | 100% LOSS OF | ℄ DURING | | SWEEPING | | | | * 2 |
| | | | | 6974 | * 2 | | | | TOTAL | 13,716 LF |

## TEMPORARY 4" WHITE LINE

PROJECT WILMINGTON

NO. HMA 2849

SHEET 7 OF 7 SHEETS

SHT. 49 OF 6