PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	LEVELING COURSE	AGGREGATE SHOULDERS	AGGREGATE SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT TYPE 3E	BITUMINOUS CONC. PAVEMENT TYPE 3E-2	POWER BROOM RENTAL	CHANGE OF ELEVATION (6 MIL)	UNIFORMED TRAFFIC OFFICERS	FLAGGERS	MOBILIZATION	TOPSOIL	
ITEM NUMBER				402.11	402.12	404.65	406.25	406.25	608.30	604.90	630.10	630.15	635.10	651.35		
UNIT	FT.	FT.	IN.	TONS/MI.	CY.	TONS	GWT.	TONS	TONS	HR.	EA.	HR.	HR.	L.S.	CY.	
LOCATION																
MM10.39~MM10.70	1636.8	40'	1.25"		—	—	9.06	—	505.2							ROADWAY
	1636.8			545'					169.0							LEVELING
MM10.70~MM10.99	1531.2	22'	1.25"				5.51	—	259.9							ROADWAY
	1531.2	4'	1.25"		—	—		—	47.3							SHOULDERS
	1531.2			354'					102.7							LEVELING
MM10.99~MM11.04	264.0	22'	1.25"				0.95	—	44.8							ROADWAY
	264.0	4'	1.25"		—	—		—	4.1							SHOULDERS
	264.0			354'					17.7							LEVELING
MM11.04~MM12.56	8025.6	22'	1.25"				24.42	—	1362.4							ROADWAY
	8025.6	4'	1.25"		—	359'	—	—	247.7							SHOULDERS
	8025.6			354					538.1							LEVELING
SHEET 14	TOTALS					359	39.94	—	3298.9							

PROJECT PUTNEY - WESTMINSTER NO. HMA 2855 SHEET 14 OF 33 SHTS.