PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	LEVELING COURSE	AGGREGATE SHOULDERS	AGGREGATE SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT TYPE IIC	BITUMINOUS CONC. PAVEMENT TYPE IIC	POWER BROOM RENTAL	CHANGE OF ELEVATION (6 MI)	UNIFORMED TRAFFIC OFFICERS	FLAGGERS	MOBILIZATION	TOPSOIL	
ITEM NUMBER				402.11	402.12	404.65	406.25	406.25	608.30	604.10	630.10	630.15	635.10	651.35		
UNIT	FT.	FT.	IN.	TONS/MI.	CY.	TONS	CWT.	TONS	TONS	HR.	EA.	HR.	HR.	L.S.	CY	
LOCATION																
WESTMINSTER MM 0.00 ~ 1.51	7972.8	23	1.25				2426		1858.4							ROADWAY
	7972.8	4	1.25		—	357	—	—	246.1							SHOULDERS
	7972.8			354					534.5							LEVELING
MM 1.51 ~ 7885	33475.2	24	1.25				1296		6199.1							ROADWAY
	33475.2	4	1.25		—	—		—	1033.2							SHOULDERS
	33475.2			382					2421.9							LEVELING
MERGES, T-H 18 & INTERSECTING RDS						10	3.00	—	50							EST.
SHEET 16 TOTALS						367	156.92	—	11838.2							

PROJECT Pitney Westminster NO. HPP 2855 SHEET 16 OF 33 SHTS.