

PROJECT ^{Purkey - Westminster} ROUTE <u>US 5</u> PROJECT # <u>HMA 2855</u>							
TEMPORARY 4' YELLOW LINE							
MILE	MILE	LT.	RT.	QTY. LEFT	QTY. RT.	TOTAL	
0.00	3.85	Solid	Solid	16104	16104	32208	
3.54	3.90	Solid	Solid	1900	1900	3800	
3.90	4.02	Solid	Dash	634	158	792	
4.02	5.46	Solid	Solid	7603	7603	15206	
5.46	5.61	Solid	Dash	792	198	990	
0.000	0.10	Solid	Dash	528	132	660	
0.10	0.14	Solid	Solid	211	211	422	
0.14	0.24	Dash	Solid	132	528	660	
0.24	0.26	Dash			26	26	
0.26	0.35	Solid	Dash	475	119	594	
0.35	0.41	Solid	Solid	317	317	634	
0.41	0.53	Dash	Solid	158	634	792	
0.53	2.69	Solid	Solid	11405	11405	22810	
2.69	2.83	Solid	Dash	739	185	924	
2.83	4.24	Solid	Solid	7445	7445	14890	
4.24	4.42	Solid	Dash	950	238	1188	
4.42	4.45	Dash			40	40	
4.45	4.57	Dash	Solid	158	634	792	
4.57	4.61	Solid	Solid	211	211	422	
4.61	4.76	Solid	Dash	792	198	990	
4.76	4.85	Dash			119	119	
4.85	5.02	Dash	Solid	224	898	1122	
5.02	8.24	Solid	Solid	17002	17002	34004	
					Sub Total	134,085	
					Assume 35 TH's @ 40' x 2 =	- 2800	
					Leveling Course + Cold Patching (50%)	+ 196,928	
						331,013	