

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT	£	QUANTITY LT	QUANTITY £	QUANTITY RT	TOTALS FEET
	3.220	3.24	Solid	Solid		106		106	212
	3.24	3.26	Solid	Solid		106		106	212
	3.26	3.28	Solid	Solid		106		106	212
	3.28	3.62	Solid	Solid		1795		1795	3590
	3.62	3.72	Solid	Solid		528		528	1056
	3.72	4.68	Solid	Solid		5069		5069	10138
	4.68	5.26	Solid	Solid		3062		3062	6124
	5.26	5.41	Solid	Broken		792		198	990
	5.41	5.55	Broken	Solid		185		739	924
	5.55	5.69	Solid	Solid		739		739	1478
	5.69	5.87	Solid	Solid		950		950	1900
	5.87	6.360	Solid	Solid		2587		2587	5174
									32010
			Assume 50% lost during leveling						16005
			32010 x 0.5 =						48015
			9 town roads @ 40' each : 9x40'x2						-720
									47295
			Rounding +5						+5
									47300LF

TEMPORARY 4" WHITE LINE

	3.220	6.360	Solid	Solid		16579		16579	33158
			Assume no losses, but deduct for intersection with 9 gravel and paved roads, total of 890'						-890
									32268
			Use						32300LF

PROJECT IRASBURG

NO. HMA 2844

SHEET 10 OF 26 SHEETS