

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT	¢	QUANTITY LT	QUANTITY ¢	QUANTITY RT	TOTALS FEET
	4.515	4.75	Solid	Solid		1241		1241	2482
	4.75	4.90	Solid	Broken		792		198	990
	4.90	5.23	Solid	Solid		1742		1742	3484
	5.23	5.37	Solid	Broken		739		185	924
	5.37	5.41			Broken		53		53
	5.41	5.51	Broken	Solid		132		528	660
	5.51	5.765	Solid	Solid		1346		1346	2692
									11285
			Assume 50% lost during leveling						
			11285 x 0.5 =						5643
									16928
			2 town roads @ 40' each: 2x40'x2						- 160
									16768
						Use			<u>16800 LF</u>

TEMPORARY 4" WHITE LINE

	4.515	5.765	Solid	Solid		6600		6600	13200
			Assume no losses, but deduct for intersection with 2 gravel roads						
			total of 65'						- 65
									<u>13135 LF</u>

PROJECT GLOVER

NO. HMA 2856

SHEET 25 OF 26 SHEETS