

TEMPORARY 4" YELLOW LINE

S = SOLID LINE  
D = DASHED LINE

EAST BOUND	MILE	MILE	LT	RT	Σ	QUANTITY LT	QUANTITY Σ	QUANTITY RT	TOTALS
	0.0	0.12	S	D			633	158	791
0.12	0.26	D	S			185	739	924	
0.26	0.66	S	S			2112	2112	4224	
0.66	0.74	S	D			422	106	528	
0.74	0.86			D			158	158	
0.86	0.98	D	S			158	634	792	
0.98	1.53	S	S			2904	2904	5808	
1.53	1.67	S	S			739	739	1478	
1.67	3.64	S	S			10402	10402	20804	
3.64	3.80	D	S			211	845	1056	
3.80	5.42	S	S			8554	8554	17108	
5.42	5.56	S	D			739	185	924	
5.56	5.61	D	S			66	264	330	
5.61	5.74	D	S			172	686	858	
5.74	6.37	S	S			3326	3326	6652	
SUB-TOTAL								62435	
ASSUME 100% LOSS DUE TO LEVELING								x 2	
								124870	
MINUS 4 ROADWAY OPENINGS @ 80' EA. X 2 COURSES OF PAINT								- 640	
								124230	
ROUNDING								270	
TOTAL								<u>124500</u>	

TEMPORARY 4" WHITE LINE

	LT	RT	TOTAL			
0.0	6.37	S	S	33634	33634	67267