

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY E	QUANTITY RT	TOTALS
1.320	1.43	Solid	Solid	581		581	1162
1.43	1.55	Dash	Solid	158		634	792
1.55	1.56	Solid	Solid	53		53	106
1.56	1.67	Solid	Dash	581		145	726
1.67	1.75	Dash	Dash		106		106
1.75	1.83	Dash	Solid	106		422	528
1.83	2.51	Solid	Solid	3590		3590	7180
0.00	0.110	Solid	Solid	581		581	1162
						Subtotal	11762
						Assume 100% loss Due to Leveling	11762
						Minus 1 Rdwy opening @ 80' Ea	- 160
						x 2 courses of pavement	
						TOTAL	23364

TEMPORARY 4" WHITE LINE

1.320	0.110	Solid	Solid	6864		6864	13728