

TEMPORARY 4" YELLOW LINE

	MILE	MILE	LT	RT		QUANTITY LT	QUANTITY RT	QUANTITY RT		TOTALS
	3.600	3.64	Solid	Solid		211		211		422
	3.64	3.70	Solid	Dash		317		79		396
	3.70	3.96	Dash	Dash			343			343
	3.96	4.08	Dash	Solid		158		634		792
	4.08	4.51	Solid	Solid		2270		2270		4540
	4.51	4.63	Solid	Dash		634		158		792
	4.63	4.77	Dash	Solid		185		739		924
	4.77	5.06	Solid	Solid		1531		1531		3062
	5.06	5.20	Solid	Dash		739		185		924
	5.20	5.32	Dash	Dash			158			158
	5.32	5.853	Solid	Solid		2814		2814		5628
								Subtotal		17981
					Assume	100% Loss Due to Leveling				17981
					Minus	8 Rdwy Openings @ 80' Ea				-1280
					x2	Courses of Pavement				
								TOTAL		34682

TEMPORARY 4" WHITE LINE

[illegible]

PROJECT 3randon

NO. HMA 2853
SHEETS 5 OF 7 SHEETS
SHEET 32 OF 75 SHEETS