

TEMPORARY 4" YELLOW LINE

S = SOLID LINE
B = DASHED LINE

	MILE	MILE	LT	RT	QUANTITY LT	QUANTITY C	QUANTITY RT	TOTALS	
LYNDON	3.346	4.13	S	S	4140		4140	8280	
	4.13	4.15	S	B	106		27	133	
	4.15	4.28	B	S	172		686	858	
	4.28	4.83	S	S	2904		2904	5808	
WHEELLOCK	0.00	0.54	S	S	2851		2851	5702	
	0.54	0.67	S	B	686		172	858	
	0.67	0.91	S	S	1267		1267	2534	
	0.91	1.04	B	S	172		686	858	
	1.04	1.57	S	S	2798		2798	5596	
SHEFFIELD	0.00	1.25	S	S	6600		6600	13200	
								SUBTOTAL	43827
								ASSUME 50% LOSS @ LEVELING +	21914
								SUBTOTAL	65741
							rounding	9	
							TOTAL	65750 LF	

TEMPORARY 4" WHITE LINE

	MILE	MILE	LT.	RT.	QUANTITY LT.	QUANTITY C	QUANTITY RT.	TOTALS
LYNDON	3.346	4.83	S	S	7836		7836	15672
HARDWICK	0.00	1.57	S	S	8290		8290	16580
STOWE	0.00	1.25	S	S	6600		6600	13200
							TOTAL	45452
							SAY	45450

PROJECT LYNDON-SHEFFIELD

NO. HMA 2834

SHEET 9 OF 30 SHEETS