

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY C	QUANTITY RT	TOTALS
0.45	0.69	S	S	1267		1267	2534
0.69	0.80	S	D	581		145	726
0.80	1.06	D	D		343		343
1.06	1.12	S	D	317		79	396
1.12	1.42	D	D		396		396
1.42	1.53	D	S	145		581	726
1.53	2.30	S	S	4066		4066	8132
2.30	2.41	S	D	581		145	726
2.41	2.66	D	D		330		330
2.66	2.78	D	S	158		634	792
2.78	3.24	S	S	2429		2429	4858
3.24	3.30	S	D	317		79	396
3.30	3.47	D	D		224		224
3.47	3.57	D	S	132		528	660
3.57	3.75	S	S	792		792	1584
3.75	3.845	S	D	502		125	627
						SUBTOTAL	= 23450
						ASSUME 100% LOSS DUE TO LEVELING	= 23450
						MINUS 4 TH'S OPENINGS @ 90' EA	= -640
						SUBTOTAL	= 46260
						ROUNDING	= 40
						TOTAL	= 46300

TEMPORARY 4" WHITE LINE

0.453	3.845	S	S	17910		17910	35820

PROJECT SWANTON

NO. HMA 2814
SHEET 11 OF 60 SHEETS