

TEMPORARY 4" YELLOW LINE

MILE	MILE	LT	RT	€	QUANTITY LT	QUANTITY €	QUANTITY RT	TOTALS FEET
3.220	3.24	Solid	Solid		106		106	212
3.24	3.26	Solid	Solid		106		106	212
3.26	3.28	Solid	Solid		106		106	212
3.28	3.62	Solid	Solid		1795		1795	3590
3.62	3.72	Solid	Solid		528		528	1056
3.72	4.68	Solid	Solid		5069		5069	10138
4.68	5.26	Solid	Solid		3062		3062	6124
5.26	5.41	Solid	Broken		792		198	990
5.41	5.55	Broken	Solid		185		739	924
5.55	5.69	Solid	Solid		739		739	1478
5.69	5.87	Solid	Solid		950		950	1900
5.87	6.360	Solid	Solid		2587		2587	5174
								<u>32010</u>
		Assume 50% lost during leveling						16005
		$32010 \times 0.5 =$						<u>48015</u>
		9 town roads @ 40' each : $9 \times 40' \times 2$						<u>- 720</u>
								47295
		Rounding +5						<u>+ 5</u>
								<u>47300LF</u>

TEMPORARY 4" WHITE LINE

3.220	6.360	Solid	Solid		16579		16579	33158
		Assume no losses, but deduct for intersection with 9 gravel and paved roads, total of 890'						<u>- 890</u>
								32268
		Use						<u>32300LF</u>