PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH		GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	POWER BROOM RENTAL	UNIFORMED TRAFFIC OFFICERS	FLAGGERS	MOBILIZATION	TEMP 4" WHITE LINE	TEMP 4" YELLOW LINE	TOPSOIL	
							OPTION									
ITEM NO.					402.10	402.12	404.65	406.25	608.30	630.10	630.15	635.10	646.50	646.51	651.35	
UNIT	FT.	FT.	IN.		CY	TON	CWT	TON	HR	HR	HR	LS	LF	LF	CY	
ESSEX																
HMA 2835	23248	28	1 1/4		1292	2261	71	5015	35	253	253	0.14	46464	86506	110	INCLUDES SHOULDERS
								1321								LEVEL COURSE
WESTFORD	6864	26	1 1/4		254	445	21	1374	10	68	68	0.04	13728	16840	33	INCLUDES SHOULDERS
HMA 2832								325								LEVEL COURSE
DRIVES & APPROACHES					25	44	—	35	—	—	—	—	—	—	—	
ROUNDING					4	—	3	30	5	4		—	8	4	7	
TOTALS	30112	VARY	1 1/4		1575	2750	95	8100	50	325	325	0.18	60200	103350	150	

PROJECT ESSEX - WESTFORD NO. HMA 2835, 2832 SHEET 17 OF 60 SHEETS