

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	UTILITIES	BRIDGE	BRIDGE - ALTERNATE 1	BRIDGE - ALTERNATE 2	FULL C. E. ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					710					710		SY	SHEET MEMBRANE WATERPROOFING (MOD. - TORCH APPLIED)	519.20	7			
					107					107		LF	METAL HAND RAILING (PAINTED)	525.15	NONE			
					511					511		LF	CAST-IN-PLACE CONCRETE BRIDGE RAIL (TEXAS)	525.50	5			
					350					350		SF	TREATED TIMBER BIN-TYPE RETAINING WALL (MOD. - SOLDIER PILE)	526.15	9			
					1					1		LS	TWO-WAY TEMPORARY BRIDGE (3000 SF - EST) (MOD.)	528.11	NONE			
					700					700		SY	REMOVAL OF BRIDGE PAVEMENT	529.10	NONE			
					1					1		EACH	PARTIAL REMOVAL OF STRUCTURE (BRIDGE)	529.20	NONE			
					1					1		EACH	PARTIAL REMOVAL OF STRUCTURE (RETAINING WALL) (STA. 14+39 RT.)	529.20	NONE			
					1					1		EACH	PARTIAL REMOVAL OF STRUCTURE (RETAINING WALL) (STA. 80+20 RT.)	529.20	NONE			
					10					10		EACH	BEARING DEVICE ASSEMBLY (ELASTOMERIC)	531.10	NONE			
					5					5		EACH	BEARING DEVICE ASSEMBLY (POT)	531.10	NONE			
													BEGIN OPTION AA					
650										650		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215	NONE			
650										650		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415	NONE			
650										650		LF	18" CPEP	601.0915	NONE			
													END OPTION AA					
													BEGIN OPTION BB					
124										124		LF	24" CAAP .060 (2-2/3 X 1/2)	601.0225	NONE			
124										124		LF	24" PCCSP .064 (2-2/3 X 1/2)	601.0425	NONE			
124										124		LF	24" CPEP	601.0920	NONE			
													END OPTION BB					
10										10		CY	DRY RUBBLE MASONRY (MOD.)	602.20	EST			
30										30		SY	STONE MASONRY FACING (MOD. - FORM LINER)	602.25	NONE			
2										2		EACH	PRECAST REINFORCED CONC. CATCH BASIN WITH CAST IRON GRATE (MOD.)	604.20	NONE			
13										13		EACH	PRC PIPE DROP INLET WITH CAST IRON GRATE (MOD.)	604.25	NONE			
				4						4		EACH	CHANGING ELEVATION OF SEWER MANHOLE	604.42	NONE			
20										20		LF	6" UNDERDRAIN	605.10	NONE			
100										100		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST			
1.5										1.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST			
			30							30		CY	STONE FILL, TYPE I	613.10	4			
			30							30		CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10	EST			
			60							60		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10	EST			
			15							15		CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10	EST			
			610							610		CY	STONE FILL, TYPE II	613.11	4			
					1050					1050		CY	STONE FILL, TYPE III	613.12	21			STONE FILL, TYPE III
710										710		LF	VERTICAL GRANITE CURB	616.21	9			178 CY PRINCE STREET LEFT SIDE
					408					408		LF	GRANITE BRIDGE CURB	616.22	NONE			122 CY PIER
250										250		LF	PRECAST REINFORCED CONCRETE CURB, TYPE A (MOD. - TEMPORARY)	616.25	NONE			729 CY ABUTMENT 2 BANK
72										72		LF	PRECAST REINFORCED CONCRETE CURB, TYPE A (MOD.)	616.25	NONE			21 CY ROUNDING
62										62		LF	CAST-IN PLACE CONCRETE CURB, TYPE B (MOD.)	616.28	9			1050 CY TOTAL

PROJECT NAME: **RANDOLPH**
PROJECT NUMBER: **BRF 0241(29)**
FILE NAME: /str5/82j096/s83j096xcl.dgn PLOT DATE: 08/25/2008
PROJECT MANAGER: W. SYMONDS DRAWN BY: G. SHANGRAW
DESIGNED BY: T. FILLBACH CHECKED BY: T. SUMNER
QUANTITY SHEET #2 SHEET 6 OF 135