

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	UTILITIES	BRIDGE	BRIDGE - ALTERNATE 1	BRIDGE - ALTERNATE 2	FULL C. E. ITEMS		GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
330										330		LF	TREATED TIMBER CURB	616.35	7			
400										400		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH (MOD.)	618.10	9			
70										70		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH (MOD.)	618.11	3			
5										5		SY	DETECTABLE WARNING SURFACE	618.30	3			
9										9		EACH	STEEL MARKER POSTS	619.16	NONE			
105										105		LF	CHAIN-LINK FENCE, 4 FEET	620.11	NONE			
600										600		LF	CHAIN-LINK FENCE, 4 FEET (MOD. - TEMPORARY)	620.11	19			
60										60		LF	REMOVAL OF EXISTING FENCE	620.55	3			
1200										1200		LF	SNOW FENCE (MOD.-PDF)	620.70	15			
675										675		LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20	NONE			
165										165		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21	NONE			
3										3		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARD RAIL	621.53	NONE			
7										7		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	NONE			
72										72		LF	REMOVL AND DISP OF GUARD RAIL	621.80	NONE			
1000										1000		LF	TEMPORARY TRAFFIC BARRIER	621.90	15			
				5						5		MFBM	INSULATION BOARD	622.10	NONE			
236										236		LF	DUCTS, CONCRETE ENCASED (8 x 4")	624.20	NONE			
				1						1		LS	DUCTS ON BRIDGE (8 x 4")	625.16	NONE			
				200						200		LF	DUCTILE, IRON PIPE, CEM LINED (12")	629.24	NONE			
				10						10		LF	DUCTILE, IRON PIPE, CEM LINED (4")	629.24	NONE			
				70						70		LF	DUCTILE, IRON PIPE, CEM LINED (8")	629.24	NONE			
				3						3		EACH	GATE VALVE WITH VALVE BOX (8")	629.27	NONE			
				1						1		EACH	HYDRANT, RELOCATE	629.29	NONE			
				1						1		LS	TRANSFER TO NEW SYSTEM-WATER SYSTEM	629.42	NONE			
				1						1		LS	WATER MAN ON BRIDGE (12")	629.60	NONE			
400										400		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST			
1500										1500		HR	FLAGGERS	630.15	204			
								1		1		LS	FIELD OFFICE-ENGINEERS	631.10	NONE			
								1		1		LS	TESTING EQUIPMENT - CONCRETE	631.16	NONE			
								1		1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17	NONE			
								1		1		LU	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	NONE			
	1040									1040		HR	EMPLOYEE TRANEESHIP	634.10	NONE			
1										1		LS	MOBILIZATION / DEMOBILIZATION	635.11	NONE			
1										1		LS	TRAFFIC CONTROL	641.10	NONE			
3100										3100		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40	26			
2700										2700		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41	12			
45										45		LF	DURABLE 8" WHITE LINE (THERMOPLASTIC)	646.42	NONE			
45										45		LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46	NONE			
23										23		EACH	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50	NONE			
80										80		LF	DURABLE CROSSWALK MARKING W/DIAGONAL LINES (THERMOPLASTIC) (MOD.)	646.51	NONE			

PROJECT NAME: **RANDOLPH**
PROJECT NUMBER: **BRF 0241(29)**
FILE NAME: jstr588j096/s88j096xcl.dgn PLOT DATE: 08/25/2008
PROJECT MANAGER: W. SYMONDS DRAWN BY: G. SHANGRAW
DESIGNED BY: T. FILLBACH CHECKED BY: T. SUMNER
QUANTITY SHEET #3 SHEET 7 OF 136