



METER DISCONNECT STANCHION
PER VAOT STANDARD E-175, DETAIL 1

RISER AT UTILITY POLE
PER VAOT STANDARD E-175, DETAIL 1.

ORNAMENTAL STREET LIGHT,
TYPICAL PER VAOT STANDARD
E-180A.

6" ELECTRICAL CONDUIT SLEEVE,
TYPICAL PER VERMONT STANDARD
SPECIFICATION 710.06

10" x 15" x 24" DEEP
OPEN BOTTOM JUNCTION BOX,
TYP. PER VAOT STANDARD E-173.

STREETLIGHTING LEGEND

----- E ----- UNDERGROUND ELECTRICAL CONDUIT -
2" PVC WITH 2#6, 1#6G CONDUCTORS

----- ES ----- UNDERGROUND ELECTRICAL CONDUIT -
3" PVC WITH 3#2 CONDUCTORS

STREET LIGHTING ON BRIDGE

PROJECT NAME: RANDOLPH
PROJECT NUMBER: BRF 024(29)

FILE NAME: /str5/88j096/sj096lg+4.dgn PLOT DATE: 29-AUG-2006
PROJECT LEADER: W. SYMONDS DRAWN BY: G. SHANGRAW
DESIGNED BY: DUFRESNE-HENRY CHECKED BY:
sj096lighting.i SHEET 87 OF 135

