STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.0 (2.16)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
13+92	STOP S													13		13		X															ERECT ONE SALVAGED SIGN ON NEW POST		
14+40	PRINCE ST FOUNDRY PARK	1 1	24 42	6 6	1.00 1.75						1			13		13		X																	E-123
18+02	RESIDENTIAL COMMERCIAL LAND S													26		26		X															ERECT ONE SALVAGED SIGN ON NEW POST		
18+92																																			
19+00	STOP	1	30	30	5.20						1			12		12		X																	E-143
19+02	← BETHEL 8	1	72	12	6.0						2											2		26							YES	REQUIRES #3-TYPE "A" FRAME SEE STANDARD E-123		E-123
	← RUTLAND 40	1	72	12	6.0																														E-123
	ROXBURY 14 ↑	1	72	12	6.0																														E-123
	SOUTH	1	24	12	2.00																														E-136B
	VERMONT 12	1	24	24	4.00																														E-136B
	← 0120 0909 0424	1 1	21 6	15 10	2.19 0.42																														E-136B E-138
												FT	FT	89 FT	FT	89 FT	FT		EA	LB	LB	LB		LB	234 LB	LB	LB								
					SF	SF	EA.	SF				FT			FT					LB			EA.	LB				EA.	EA.	LB					
					SUB TOTAL							89			89								2	234											
					GRAND TOTAL																														

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT NAME: RANDOLPH
PROJECT NUMBER: BRF 0241 (29)

FILE NAME: /str5/88j096/sj096ts2.dgn
PROJECT LEADER: W. SYMONDS
DESIGNED BY: G. SHANGRAW
sj096ss1.i
PLOT DATE: 29-AUG-2006
DRAWN BY: G. SHANGRAW
CHECKED BY: T. SUMNER
SHEET 102 OF 135