

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	BRIDGE NO. 155	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								237		237		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
								3.3		3.3		CWT	EMULSIFIED ASPHALT	404.65				
							1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								10		10		GAL	WATER REPELLENT, SILANE	514.10				
								40		40		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								109		109		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								40		40		LF	JOINT SEALER, HOT POURED	524.11				
								109		109		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
								10		10		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS I	580.10				
								20		20		SY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS II	580.11				
								5		5		CY	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE, CLASS III	580.12				
								977		977		SF	SURFACE PREPARATION FOR MEMBRANE	580.16				
								5		5		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20				
								360		360		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
								3		3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56				
								2		2		EACH	REPLACE GUARDRAIL POST ASSEMBLY	621.76				
								1		1		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77				
								220		220		LF	TEMPORARY TRAFFIC BARRIER	621.90				
								220		220		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
								360		360		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
								160		160		HR	FLAGGERS	630.15				
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
									1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1			1		LS	MOBILIZATION/DEMobilIZATION	635.11				
								1		1		LS	TRAFFIC CONTROL	641.10				
								2		2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
								1085		1085		LF	4 INCH WHITE LINE	646.20				
								1085		1085		LF	4 INCH YELLOW LINE	646.21				
								2010		2010		LF	TEMPORARY 4 INCH WHITE LINE, TYPE II TAPE	646.601				
								1085		1085		LF	TEMPORARY 4 INCH YELLOW LINE, TYPE II TAPE	646.611				
								22		22		LF	TEMPORARY 24 INCH STOP BAR, TYPE II TAPE	646.681				
								589		589		SF	PAVEMENT MARKING MASK	646.86				
								1		1		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620				
								1		1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
								1		1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
								63		63		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				