PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	GRAVEL SHOULDERS	GRAVEL SHOULDERS (OPTION)	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	CHANGE ELEV. OF CB, DI, OR MH	ALL PURPOSE EXCAV.	POWER BROOM RENTAL	RENTAL TYPE I	UNIFORMED TRAFFIC OFFICERS	FLAGPERSONS	MOBILIZATION	TEMP. PAVT. MARKING-WHITE	REMARKS
ITEM NUMBER			402.10	402.11	404.65	406.25	604.40	608.25	608.30	630.10	630.15	635.10	646.35			
UNIT	FEET	FT	INCH	C.Y.	TON	CWT	TON	EA	HR	HR	HR	HR	LS	L.F.		
LOCATION																
ESSEX MM1.227~MM2.000	4080	22				25	213									LEVELING @250 TONS/MI.
		22	1¼				693									WEAR COURSE "
ESSEX MM2.000~MM2.200	1056	23				7	58									LEVELING @250 TONS/MI.
		23	1¼				187									WEAR COURSE "
ESSEX MM2.200~MM2.557	1883	22				11	98									LEVELING @250 TONS/MI.
		22	1¼				320									WEAR COURSE "
ESSEX MM2.557~MM3.303	3941	22				24	205									LEVELING @250 TONS/MI.
		22	1¼				669									WEAR COURSE "
DRIVES & APPROACHES				100	165		250									
PROJECT (EST)								5	20	17	62	62	0.	21,922		SEE SHEET 60 OF 60 FOR DETAILS
SHOULDERS - PROJECT				2200	3630	15	806*		90	100	200	200				*INCLUDES ALLOWANCE FOR TAPERS & PATCHING
ROUNDING						3	101		10	3	38	38		28		
TOTALS PAGE	10,960			2300	3795	85	3600	5	120	120	300	300	0.	21,950		

PROJECT ESSEX NUMBER M-5400(3)5 SHEET 17 OF 60