

PC 13170.50
D- 6°
Bank 0.42/ft
(to match existing)

13+58 Lt
Begin Guard Rail (Standard Spacing)
Beam w/ Wood Posts, Type II
Item 621.28

ROW
24.75

13+50 Lt
Construct Drive

Note: All Embankment will be Granular
Borrow, Item 203.32 unless
labeled otherwise.

13+00-
MM 1.05
Begin Common Excavation, Item 203.13
Begin Subbase of Gravel, Item 301.15
Begin 5" Plant Mixed Base Course Item 303.25
Begin 1 1/4" Course of Bituminous Concrete Pavement, Type D, Item 406.25

Note: All Material Excavated will be Disposed of
Off the Site or as Directed by the Engineer.
Two Way Traffic Will Be Maintained During
The Hours of Darkness.