QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

TRAINING	EROSION CONTROL				NON-GVMT PART.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	45					481	550	CY	STONE FILL, TYPE I	613.10	24
						610	610	CY	STONE FILL, TYPE II	613.11	
						710	710	LF	GRANITE SLOPE EDGING, (MOD.)	616.20	8
						2370	2370	LF	VERTICAL GRANITE CURB	616.21	22
						2125	2125	LF	TREATED TIMBER CURB	616.35	24
						8450	8450	LF	REMOVING AND RESETTING CURB	616.40	27
						1400	1400	LF	REMOVAL OF EXISTING CURB	616.41	34
						22	22	TON	BIT. CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	1
						505	505	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5''	618.10	
						4	4	EA	BOUNDARY MARKERS	619.10	EST.
						39	39	EA	YIELDING MARKER POST	619.17	-
						5947	5947	LF	STEEL BEAM GUARD RAIL	621.20	-
						100	100	LF	STEEL BEAM GUARD RAIL (W/8' POSTS)(MOD.)	621.20	EST.
						5	5	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.52	-
						2	2	EA	ANCHOR FOR STEEL BEAM GUARD RAIL	621.60	-
						3250	3250	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	22
						1000	1000	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
						1000	1000	HR	FLAGGERS	630.15	EST.
						1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
						1	1	LS	FIELD OFFICE TELEPHONE (NABI)	631.25	-
520							520	HR	EMPLOYEE TRAINEESHIP	634.10	EST.
						1	1	LS	MOBILIZATION	635.10	EST.
						1	1	LS	TRAFFIC CONTROL	641.10	EST.
						800	800	LF	PAINTED CURB	646.27	-
						14005	14005	LF	DURABLE 4'' WHITE LINE	646.40	-
						10560	10560	LF	DURABLE 4'' YELLOW LINE	646.41	-
						1410	1410	LF	DURABLE 8'' WHITE LINE	646.42	-
						190	190	LF	DURABLE 8'' YELLOW LINE	646.43	-
						145	145	LF	DURABLE 24'' STOP BAR	646.46	-
						87	87	EA	DURABLE LETTER OR SYMBOL	646.50	-
						42015	42015	LF	TEMPORARY 4'' WHITE LINE	646.60	-
						31680	31680	LF	TEMPORARY 4'' YELLOW LINE	646.61	-
						4230	4230	LF	TEMPORARY 8'' WHITE LINE	646.62	-
						570	570	LF	TEMPORARY 8'' YELLOW LINE	646.63	-
						435	435	LF	TEMPORARY 24'' STOP BAR	646.66	-
						87	87	EA	TEMPORARY LETTER OR SYMBOL	646.70	-
						1000	1000	EA	LINE STRIPING TARGETS	646.73	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

SURVEYED BY	DATE
DRAWN BY SQUAD A	DATE 8-92
SQUAD LEADER BTN	
DESIGN FILE NO. /sqdo/89b018/db018.dgn	
IFARM FILE db018qs2.1	DATE PLOTTED 12-MAR-1996
PROJ. NAME MONTPELIER	
PROJ. NO. FEGC-F 028-2(8)	
SHEET 7 OF 118 SHEETS	

: Sheet Number: 7