



STEEL BEAM GUARDRAIL  
 6+75 RT - 30+75 RT  
 REMOVE EXISTING GUARDRAIL  
 12+15 RT - 26+00 RT  
 COLD PLANING-BIT. PAVEMENT  
 0+00 - 47+50

TREATED TIMBER CURB  
 7+00 RT - 19+50 RT  
 REMOVE AND RESET EXISTING CURB  
 17+05 LT - 18+80 LT

CONSTRUCT SPECIAL DITCH W/STONE FILL TYPE I  
 7+50 RT - 17+00 RT

**CURVE DATA**  
 Δ = 31°10'24" RT  
 D = 6°00'00"  
 R = 954.93  
 T = 266.38  
 L = 519.56  
 E = 36.46

**DRAINAGE NOTES**

- 20 12+00 - 14+00 RT NEW 18" X 200" RCP CL III W/RCDI AT INLET
- 21 14+00 - 16+00 RT NEW 18" X 200" RCP CL III W/RCDI AT INLET
- 22 15+50 RT NEW 4' X 18" CSP (.064) ; CONSTRUCT NEW HEADWALL
- 23 16+00 - 18+42 RT NEW 18" X 242" RCP CL III W/RCDI AT INLET
- 24 18+42 RT REMOVE EXIST. HEADWALL, EXTEND EXIST 18" PIPE, CONSTRUCT RCDI

THIS SHEET  
 FOR ROW  
 USE ONLY

SURVEYED BY Fall DATE 5-90  
 DRAWN BY Squade-Jfg DATE 6-90  
 SQUAD LEADER D.F.Hole  
 FILE UBT/2102/055050.dwg/89b018  
 IPARM FILE 89B018.31 DATE 03/30/90  
 PROJ. NAME **MONTPELIER**  
 PROJ. NO. **FECC-F 028-2(B)S**  
 SHEET 6 OF 15 SHEETS

DATUM  
 VERTICAL NGVD 1929  
 HORIZONTAL N/A

