STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

APPROXIMATE SUMMARY OF QUANTITIES

	R.O.W.			NON-GOV'T PARTICIPATING	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
						30	30	m^3	COMMON EXCAVATION	203.15	-
						825	825	m^3	EARTH BORROW	203.30	5
						1	1	m^3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	-
						34700	34700	m^2	COLD PLANING - BITUMINOUS PAVEMENT	210.10	674
						820	820	T	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	9
						1950	1950	T	AGGREGATE SHOULDERS	402.12	46
						21200	21200	KG	EMULSIFIED ASPHALT	404.65	386
						23900	23900	T	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)	406.30	307
						1	1	LS	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
					1		1	CM	CONCRETE, CLASS A	501.22	0.4
									BEGIN OPTION ITEMS		
					40		40	M	JOINT SEALER, HOT POURED	524.11	4
					40		40	M	JOINT SEALER, COLD POURED	524.13	4
									END OPTION ITEMS		
					76		76	M	BRIDGE RAILING-HEAVY DUTY STEEL BEAM/ CURB MOUNT. (MOD 2)	525.40	-
					1		1	CM	REMOVAL OF CONCRETE OR MASONRY	529.25	EST.
						7	7	EA	CHANGE ELEVATION OF DI'S, CB'S, MH'S	604.40	-
						1	1	EA	REHAB. OF DI'S, CB'S OR MH'S, CLASS I	604.412	-
						1	1	EA	REHAB. OF DI'S, CB'S OR MH'S, CLASS II	604.415	-
						1	1	EA	REHAB. OF DI'S, CB'S OR MH'S, CLASS III	604.418	-
						280	280	HR	POWER GRADER RENTAL (NOT A BID ITEM)	608.15	EST.
						280	280	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I (NOT A BID ITEM)	608.25	EST.
						170	170	HR	POWER BROOM RENTAL (NOT A BID ITEM)	608.30	EST.
						280	280	HR	TRUCK RENTAL (NOT A BID ITEM)	608.37	EST.
						280	280	HR	LOADER RENTAL, TYPE I (NOT A BID ITEM)	608.40	EST.
						40	40	T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	3
						627	627	M	STEEL BEAM GUARD RAIL	621.20	26.6
						3914	3914	M	STEEL BEAM GUARD RAIL (MOD.)	621.20	41.8
						228	228	M	HEAVY DUTY STEEL BEAM GUARD RAIL	621.21	1.2
						41	41	EA	MODIFIED ECCENTRIC LOADER TERMINAL	621.54	-
						56	56	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	-
						22.5	22.5	M	ALUMINUM APPROACH RAIL	621.74	-
						7.5	7.5	M	ALUMINUM APPROACH RAIL (MOD.)	621.74	-
						38	38	M	REMOVING AND RESETTING GUARD RAIL	621.75	15.2
						3850	3850	M	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	30.7
						1100	1100	HR	UNIFORMED TRAFFIC OFFICERS(NOT A BID ITEM)	630.10	EST.
						1600	1600	HR	FLAGGERS(NOT A BID ITEM)	630.15	EST.
						1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-
						1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
						1	1	LS	FIELD OFFICE - TELEPHONE (N.A.B.I.)	631.25	-
						1	1	LS	MOBILIZATION	635.10	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING - BITUMINOUS PAVEMENT
29037	m^2	JERICHO STA. 0+000.0 TO 3+218.7
757	m^2	BRIDGES
1038	m^2	SIDE ROADS
216	m^2	BEGIN APPROACH
1651	m^2	TRANSITIONS
1125	m^2	JERICHO STA. 5+133.0 TO 5+258.0
202	m^2	END APPROACH
674	m^2	ROUNDING
34700	m^2	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 58-28)
3667	T	LEVELING COURSE
7195	T	TYPE II
12364	T	TYPE III (WEARING COURSE)
131	T	SIDE ROADS
175	T	PULLOUTS
61	T	DRIVES
307	T	ROUNDING
23900	T	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	METERS	KILOMETERS	REMARKS
TOTALS									

FINAL QUANTITIES ARE ARCHIVED WITH THE FIELD BOOKS

ARCHIVED IN DPR

QUANTITY SHEET #1
23-SEP-2009 09:45
/pave/92b22l/pb22l.dgn

PROJECT NAME: ESSEX - UNDERHILL
PROJECT NUMBER: STP 9469(1)S

pb22lqsl.1
SHEET 5 OF 40 SHEETS